BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-01/2020-21 Dt:02-5-2020

APPROVED TENDER SCHEDULE –'B'

Item 01

Name of Work :-Emergency works in ward limits in kempegowda ward no -01 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri B K NAGENDRA	
				Rate	Rate in Words
1	KSRB 2 2 1 Earthwork excavation by manual means for foundation of buildings culverts water supply and sanitary lines and electrical conduits etc either in pits or in trenches 1 5m and above in width in ordinary soil not exceeding 1 5 m in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear from edges of excavation with lead up to 50 m including breaking of clods complete as per specifications No KBS 2 1 a Item No 2 3 5 Page no 6	Cum	1032.30	288.00	Two Hundred EightyEight Only
2	KSRB M100 1 Loading and unloading ofstone aggregates Stone sand kaner Moorum soilKSRRB M100 1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulgeand return trip complete as per specification item No 17 1 page 117 and KSRB M 100 4 1 costof haulage excluding loading and unloading MORTH to a distance of 4 00 K.M with all lead and lift etc complete as per specification and direction of engineer incharge of the work	Cum	1032.30	79.00	SeventyNine Only
3	Supplying and fixing precast reinforced cement concrete slab 10 cm Thick including cost of reinforcement as per design and drawing material cost transportation hire charges of machinery machine cutting the vertical face to get plain even surface etc complete with all leads and lift conveyance charges labour charges inclusive of cost of all materials Drain covering slab	Sqm	435.00	2021.00	Two Thousand TwentyOne Only

	Providing precast slab of 250mm tick including cost of all materials labour curing, transportation loading unloading etc complete as per the direction.	Sqm	50.00	4925.00	Four Thousand Nine Hundred TwentyFive Only
5	Engaging on Hire Basis JCB including Driver operator with fuel etc complete SR 2018-19 Page No XLVIII code 1031 of engineer in charge	Day	45.00	5165.00	Five Thousand One Hundred SixtyFive Only
6	Engaging on Hire basis of Tractor 50 HP for Conveying of excavated and removal of Stuff from work spot SR 2018-19 Page No XLVIII code 1024	Day	90.00	1930.00	One Thousand Nine Hundred Thirty Only
7	Labour charges to Unskilled Mazdoor Heavy Page no LVI SR 2018-19 sl No 5	Day	1170.00	446.20	Four Hundred FourtySix Paise Twenty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.